

2. SEE SHEET C001 FOR GENERAL NOTES AND LEGEND.
3. SEE SHEET C001 & C502 FOR ADDITIONAL EROSION & SEDIMENT CONTROL NOTES AND DETAILS.
4. UPON AWARD OF THE CONTRACT AND PRIOR TO ANY LAND DISTURBANCE, CONTRACTOR SHALL DESIGNATE A PERSON TO ACT AS THE EROSION & SEDIMENT DEPARTMENT OF ENVIRONMENTAL QUALITY (VA DEQ) AS A RESPONSIBLE LAND DISTURBER (RLD) FOR THIS PROJECT. NOTIFY THE COUNTY IN WRITING OF THIS DESIGNATION, NAME OF RLD AND PHONE NUMBER. THIS NOTIFICATION SHALL BE SUBMITTED TO THE COUNTY PRIOR TO PRE-CONSTRUCTION MEETING.
5. EROSION & SEDIMENT CONTROL DEVICES AND MEASURES FOR PROPER INSTALLATION AND DEFICIENCIES IMMEDIATELY AFTER EACH RAINFALL, AT LEAST DURING PROLONGED RAINFALL, AND WEEKLY WHEN NO RAINFALL EVENT OCCURS. THE EROSION & SEDIMENT CONTROL PLAN SHALL BE MAINTAINED IN THIS PLAN IS A PART OF THE PLANS AND SHALL BE USED IN CONJUNCTION WITH THE PLANS.
6. AS THE EROSION AND SEDIMENT CONTROL PLAN APPROVING AUTHORITY, THE COUNTY MAY REQUIRE THE CONTRACTOR TO TAKE ADDITIONAL MEASURES TO PREVENT EROSION, INADEQUATE TO SATISFY APPLICABLE REGULATIONS.
7. STORE EXCAVATED TOPSOIL IN TOPSOIL STOCKPILES WITHIN THE LIMITS OF DISTURBANCE. TOPSOIL STOCKPILES SHALL BE COVERED WITH VEGE MATS, MULCH, SEED AND STRIP MULCH ALL SOIL STOCKPILES WITHIN 7 DAYS IF THEY WILL REMAIN DORMANT FOR MORE THAN 90 DAYS.
8. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
9. EXCAVATION DEEPER THAN 500 LINEAL FEET SHALL BE OPENED AT ANY TIME.
10. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
11. VEHICLES ENTERING AND LEAVING THE SITE SHOULD REMAIN ON PAVED SURFACES TO AVOID TRACKING SOIL ONTO UNPAVED AREAS.
12. WHERE SEDIMENT IS TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE, THE SURFACE SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED TO THE NEAREST EROSION & SEDIMENT CONTROL FACILITY OR TO THE EROSION & SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED FROM THE ROAD SURFACE.
13. SHOULD Dewatering Operations become necessary, Effluent shall be filtered and discharged in a manner that does not adversely affect flowing streams or off-property.
14. IF OFF-SITE AREAS ARE REQUIRED FOR BORROW OR WASTE SITES AS PART OF THE LAND DISTURBANCE ASSOCIATED WITH THIS PLAN, A SEPARATE EROSION & SEDIMENT CONTROL PLAN SHALL BE SUBMITTED TO THE COUNTY FOR REVIEW AND APPROVAL.

1. INSTALL INLET PROTECTION ON EXISTING STORM STRUCTURES (INCLUDING IMMEDIATELY DOWNSTREAM)
2. INSTALL SILT FENCE.
3. INSTALL SAFETY FENCE (ADJUST LIMITS AS NEEDED AS CONSTRUCTION PROGRESSES)
4. INSTALL TREE PROTECTION.
5. REMOVE TREES, BRUSH, ETC. ACCORDING TO DEMOLITION PLAN.
6. REMOVE SIGNS, BOLLARDS, ETC. AS NOTED ON DEMOLITION PLAN.
7. COMPLETE DEMOLITION OF SIDEWALKS, CURBING, PAVEMENT, ETC.

